

Recommendations:

Because of the size of mound systems required on lots # 6 and 7 and the unsuitability of lot # 8, it is recommended that those lots be redesigned by combining lots # 7,8, + 9 into two lots with equal road frontage. In that manner mound systems could be effectively designed for those two lots.

I certify that the soil types were identified in accordance with standards developed in the National Cooperative Soil Survey.



Darryl N. Brown